Fame of Range	Name of Forest	Length of the line	Rate per mile	Amount
		Ml. F.	Rs. a. p.	Rs. a. p.
Molakalmuru ..	Doddachallur (Exterior)	7 0		
	Obenahalli	12 3		
	Hireadvi	17 0		
	Do (Working Circle line)	3 0		
	Kamarakaval (Exterior)	24 4		
	Do (Interior)	6 0		
	Konsagara (Exterior)	10 4		
	Krishnarajapur (Exterior)	25 0		
	Sanjeevarayankote (Exterior)	17 0		
	Santhebande	15 0		
	Bondravi	14 0		
	Mallurahalli	12 0		
	Obannanahalli	8 2		
Chitaldrug ..	Jogimatti	49 0		
	Rangayyandurga	59 0		
	Do (Block line)	7 0		
	Anabur (Exterior)	30 4		
	Do (Block line)	6 0		
	Jagalur block (Exterior)	11 2		
	Guheswaragudda (Exterior)	10 0		
Hiriyur Range ..	Lakkihalli	31 0		
	Marikanive	34 4		
	Swarnamukhi	26 2		
	Kudurekanive	40 6		
	Gowdanahalli	15 0		

L. SRINIVASA MURTHI,
District Forest Officer.

ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 9th September 1939.

The attention of the public is hereby invited to the detailed notification, calling for tenders for constructing the extension of Women's Hostel, Locksley Hall, Bangalore, published in pages 1856-1858, Part VI of the *Mysore Gazette*, dated 14th September 1939. The last date of tender is 30th September 1939.

M. K. RAJAM IYENGAR,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notification dated 11th September 1939.

The attention of the public is invited to the notification, calling for tenders for the work of constructing drains in Coimbatore Colony and extension in Hiriyur Town, published in pages 1898-1899, Part VI of the *Mysore Gazette*, dated 14th September 1939.

The last date of receiving tenders is fixed on 2nd October 1939.

N. KRISHNIENGAR,
Sanitary Engineer.

KOLAR DIVISION.

Notification dated 19th September 1939.

1. Sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th October 1939, for maintenance work to Nambihalli Doddakere, Reg. No. 93—426 of Srinivaspur Taluk.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Maintenance work to Nambihalli Doddakere. Reg. No. 93—4626 of Srinivaspur Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by Treasury challan for earnest money of Rs. 175 paid to the treasury to the credit of 17 (a) P. W. Deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 16th October 1939 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. Where lumpsum provisions are shown in the schedule of quantities, the contractor will be paid at either his tendered rate for such item or the prevailing schedule of rates in the division.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of dispute of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date

of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations whenever and whenever necessary with his own pumping apparatus including necessary leading drains, sump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P.W.D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on payment of four annas per form.

Abstract of quantities for maintenance work of Nambihally Doddakere, Register No. 93–426 of Srinivaspur Taluk.

Sl. No.	Details of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Jungle clearing and removing roots, etc., complete ..	Grade	0 8 0	41
2	Cutting grips and trenches	„	2 0 0	41
3	Earthwork to bund with watering and tamping including lead and lift	C.yd.	0 3 0	13,519
4	Turfing front and rear slopes	S.yd.	0 0 9	16,582

Notification dated 19th September 1939.

Sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th October 1939, for construction of Quarters for the Inspector of Mines and Explosives at Kolar Gold Fields.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for construction of Quarters for the Inspector of Mines and Explosives at Kolar Gold Fields. The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by treasury challan for earnest money of Rs. 550 paid to the treasury to the credit of 17 (a) P. W. Deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 16th October 1939 at 2 P.M. at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be with held in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days, between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. Where lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate from each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar only on a payment of four annas per form.

Abstract of quantities for construction of Quarters for the Inspector of Mines and Explosives at Kolar Gold Field

Sl. No.	Items of work	Unit	Rate	Quantity	Rate to be offered
			Rs. a. p.		
1	Earth excavation for foundation and filling in basement	C.yd.	0 3 6	209	
2	Laying stone jelly concrete in chunam mortar ..	C.ft.	0 3 3	1,562	
3	Burnt size stone in mortar foundation with necessary bond stones	„	0 1 3	3,358	
4	Size stone in chunam mortar basement including dressing quoins and bond stones, etc., complete	„	0 4 9	1,111	
5	Size stone in chunam mortar superstructure with necessary bond stones	„	0 5 0	6,088	
6	Burnt brick in chunam mortar superstructure ..	„	0 4 3	228	
7	Teakwood doors with 3½"×5" frame and 1½" thick panelled shutters including hinges, bolts fittings, etc., 1st class varnish complete ..	S.ft.	1 6 6	50	
8	Teakwood doors with [illegible] thick flattened shutters including hinges, etc., complete ..		2 4 0	156	
9	Teakwood windows with [illegible] frame and 1½" thick shutters half-panelled and half-glazed including iron bars, bolts and hinges, etc., complete		2 0 0	152	
10	Teakwood rectangular ventilators with glazed shutters and iron bars, etc., complete ..	„	1 3 0	151	
11	Teakwood almirahs with panelled shutters and partitioning planks inside, etc., complete	„	1 8 0	48	
12	Burnt stone slabs 6" thick, [illegible] including supplying [illegible] for ..		0 5 6	1,145	
13	Tata's [illegible] including supplying hoisting [illegible] and painting with a priming [illegible] corrosive paint, etc., complete	C.ft.	15 3 0	27·5	
14	Teakwood 1st class [illegible] and put up including two coats of wood oil	C.ft.	5 [illegible] 0	239·5	
15	Roofing with Madras terrace with a cambre of 1 in 40 on bottom terrace laid with burnt brick on edge and 3" thick [illegible] terrace with brick jelly well beaten and [illegible] flat tiles laid at top diagonally [illegible] plastering at top and bottom smooth ..	Sqr.	25 [illegible]	19·75	
16	Roofing with 1st class Mangalore tiles on Teakwood reepers including wood edging, etc., complete	Sqr.	28 0 0	3·99	
17	Mangalore Ridge tiles set in cement mortar ..	R.ft.	0 7 6	42	
18	Chunam mortar plastering, two coats to stone walls inside	Sqr.	[illegible] 0	69·67	

Sl. No.	Items of work	Unit	Rate	Quantity	Rate to be offered
			Rs. a. p.		Rs.
19	White washing, two coats	Sqr.	0 4 0	69·67	
20	Cement pointing to exterior walls and basement including raking joints	,,	3 0	29·83	
21	Providing burnt stone slabbed cornice 6" wide including blocking course and exposed surface neatly dressed and finished is per design	R.ft.	0 7 0	268	
22	Burnt size stone in chunam mortar parapet 1½' to 2' high including coping slabs one line dressed and cement pointing, etc., complete as per design	,,	1 4 0	283	
23	Providing and fixing C.I. Rain-water down pipes of 3" dia. including painting, etc., complete.	,,	0 12 0	150	
24	Burnt brick in mortar wall 4½" to 6" thick with ext et at every third course including plastering and white washing, etc., complete	S.ft.	0 10 0	161	
25	R.C.C. Chajja 4" to 6" thick including re-inforcement bars and plastering all exposed faces smoothening, etc., complete	C.ft.	1 4 0	76	
26	Boxing girders with burnt brick in cement mortar and wire net and plastering the wire net with cement mortar	R.ft.	0 12 0	129	
27	Flooring with cement concrete 1 : 2 : 4 to 1½" thick on a bed of 6" thick lime concrete and at top 1" thick red oxide cement plastering and finished neatly	Sqr.	20 0 0	19·00	
28	Flooring with stone jelly concrete in lime mortar 3" thick and top plastered with ½" thick cement mortar	,,	15 0 0	2·40	
29	Painting two coats the exterior surface of doors and windows with green paint prepared in the Mysore Government Lac Factory including conveying charges, etc., complete	,,	4 4 0	2·68	
30	Dulex Varnishing, two coats	,,	1 0 0	8·94	
31	Two line dressing to quoins 2" wide superstructure and corners of walls, etc.	R.ft.	0 3 0	250	
32	Cut stone pillars 9" square and 8' high including base and capital, etc., complete and nicely dressed as per design to be furnished	Each	15 0 0	5	
33	Providing plain Teakwood eave board 1" thick and 9" deep including painting, etc., complete	R.ft.	0 7 6	104	
34	Providing mortar band 4½" wide over gable ends including plastering, etc., complete	,,	0 3 6	32	
35	Archwork with size stone voussoir fixed in chunam mortar including centering	C.ft.	0 7 3	38	
36	Providing Teakwood partition including wood oiling, etc., complete	L. S.			
37	Construction of a latrine with necessary drainage arrangements	,,			
38	Construction of a Motor Garage	,,			
39	Providing smoke escapes in the kitchen and bath rooms	,,			
40	Providing sinks in the bath and kitchen rooms	,,	*	*	*
41	Excavation of trial pits and clearing site, etc., complete	,,			
42	Miscellaneous and unforeseen charges	,,			
	Providing water supply	,,			
	Providing Electric Lights	,,			

* Contractors will be paid for these L. S. items as per his tendered rates and for non-tendered items as per Schedule rates.

C. R. IYENGAR,
Executive Engineer.

6 E